

1 Stop Modular Safety Review/Orientation

General Safety Notes

- 1 Stop Modular is committed to sending people home in the same condition as they arrived to job in.
- Safety must be taken into consideration with every aspect of the job and is everyone's responsibility.
- **WE MOVE BUILDINGS!** Always pay attention to surroundings on jobsite (Buildings/Machines/Heavy Equipment/Trucks and Etc.)
- Stay clear of anything bigger than you (Buildings/Machines/Heavy Equipment/Trucks/Etc.)
- No cell phone use during working hours.
- Keep feet and body away from all wheels/tires from any source.
- Watch for and expect lash back on come alongs, winches, chains and binders.
- Always build a solid level base for bottle jacks/tracks and rollers/cribs.
- Always expect/watch for/prepare for a building on bottle jacks to fall.
- No music ear phones/ear buds/head phone use during working hours.
- Follow and obey site specific jobsite safety rules and regulations.

Signals/Whistles/Horns

- 3 quick beeps = Machine moving forward pushing dollies.
- 1 quick 1 long beep = Machine moving reverse pulling dollies.
- 3 quick beeps = Building being raised or building being lowered.
- Whistle = All Stop.

Cribs

- Never go under a building that does not have landing gear or is not cribbed.
- Always crib building before working under building.
- Always make crib base level/sandy conditions require abs base pad.
- Never trust anything but a crib.
- Never trust bottle jacks or equipment when working under building.
- If in doubt Crib/Crib/Crib.

PPE

- Boots/Long pants/Safety glasses/Gloves to be worn or utilized always on every job.
- Hard hats/High vis vest are currently site specific.
- Boots/Long pants/Safety glasses/Gloves are your responsibility to maintain and or replace.

Ladders

- Extension ladder/always to be set up 3 rungs above landing and tied off.
- A-frame ladders/always level ground so that all 4 feet are stable with no feet floating.
- Always 3 of 4 limbs attached to ladders.
- No walking ladders/no standing on top rung.
- Obey the warning labels.

Pinch Points/Mate Line

- Learn to recognize and avoid pinch points always.
- Watch for pinch points on equipment and buildings.
- Pinch points include all of forklift mast, top of pier and bottom of chassis, entire mate line when setting a floor to a set floor.
- Do not put limbs or digits in pinch points of any sort, the limb or digit may not return.
- Absolutely no body or limbs are to be in between floors of building (mate line) while install/dismantle of building.

I understand and agree to follow 1 Stop Modular Safety Review/Orientation and to be vigilant with all safety hazards listed and not listed above

Print Name: _____

Sign Name: _____

Date: _____